





INCA FISH CAGE SYSTEM

SPECIFICATIONS:	AQUA CAGE 10-meter diameter Double collar stanchions	AQUA CAGE 15-meter diameter Double collar stanchions	ECONOCAGE (For high value species) 4m x 4m x 4m 4units (1 module) Single stanchions	LOW VOLUME HIGH DENSITY (LVHD) Fish Cage. Suitable for Fisherfolk fish cage operations
Cage float	225 mm diameter UV-stabilized double collar High Density Polyethylene (HDPE) floatation with polystyrene inserts, roto-molded PE stanchions, 75mm diameter UV-stabilized black PE handrail		225 mm diameter UV-stabilized High Density Polyethylene (HDPE) Pipe with polystyrene inserts, 38mm dia. plastic stanchion posts with 25mm dia. polyethylene pipe hand railing, HDPE connectors and 1"x10" wooden walkway	One piece rotomolded cage float measuring 3 meter x 2.3 meter x 4 meter net depth. With total net volume of 25 cbm. No assembly needed.
Nursery net	4 meter depth 400/9 x 17K knotted PE net, square mesh, S/S tie rings		4 units 4m x 4m x 2m depth, SD 24K knotless square mesh, PE tie rings	1 unit 3m x 2.3m x 2m depth, SD 24K knotted square mesh, PE tie rings
Grow-out net	6 meter depth 400/15 x 10K knotted PE net, square mesh, S/S tie rings		4 units 4m x 4m x 4m depth, 400 / 15 x 17K knotted PE, square mesh, S/S tie rings	1 unit 3m x 2.3m x 4m depth, 400 / 15 x 17K knotted PE, square mesh, S/S tie rings
Net Cover	Knotted PE net		Knotted PE net. (4m x 4m)	Knotted PE net (3mx2.3m)
Net weights	12 units PE casing, 20 kg. Ferro-cement weight with stainless handle and quick release hook	15 units PE casing, 20 kg. Ferro-cement weight with stainless handle and quick release hook	32 units PE casing, 10-kg Ferro-cement weight with stainless handle and quick release hook.	4 units PE casing, 10-kg Ferro-cement weight with stainless handle and quick release hook.
Mooring	4 units 1-ton Ferro-cement anchor, 30 mm PP anchor rope, counter weights and 200 liter cushion floats		6 units Ferro-cement anchor, 30 mm PP anchor rope	4 units Ferro-cement anchor, 30 mm PP anchor rope
Delivery	15 to 30 working days upon mobilization			
PHOTOS:	   			
Assembly & Installation	Buyer to provide for free, reasonable lodging for 3 technicians, Security at site until completion, 220V / 10 KW power supply or 10 KVA genset with fuel, boat to tow the cage and to ferry anchors to cage site during cage assembly work			
	INDICATIVE PRICE vat excluded and FOB Muntinlupa City:			
	PHP 352,000	PHP 485,000	PHP 332,000	PHP 60,000
Cage float	PHP 440,000	PHP 575,000	PHP 425,000	PHP 70,000
Cage float w/ nets COMPLETE	PHP 510,000	PHP 645,000	PHP 486,000	PHP 80,000